

Batterman


DETAILS


CHARTER FIBER OPTIC INSTALLATION RDOF - JN16E TOWN OF AZTALAN & LAKE MILLS JEFFERSON COUNTY, WISCONSIN

SHEET NO.

C3.02

# TYPES OF PEDESTALS USED DURING CONSTRUCTION CHARLES PED 7500 (LG) CHARLES PED 9500 (XLG)





**Batterman** engineers surveyors planners


PEDESTAL DETAILS

CHARTER FIBER OPTIC INSTALLATION RDOF - JN16E TOWN OF AZTALAN & LAKE MILLS JEFERSON COUNTY, WISCONSIN

C3.03

## TYPES OF VAULTS USED DURING CONSTRUCTION






|   |          | Α             | В                | C                 |
|---|----------|---------------|------------------|-------------------|
| Ī | SGLB1730 | 24" (609.6mm) | 21.75" (552.5mm) | 33.25" (845.0mm)  |
|   | SGLB2436 | 24" (609.6mm) | 28.5" (723.9mm)  | 40.25" (1022.4mm) |

Channell's SGLB1730 and SGLB2436 "Shutter Box" Series SGLBs have the highest strength/deflection ratings in the industry.

|             | Solid Thermoplastic Cover | Split Thermoplastic Cover | Polymer Concrete with Ring |
|-------------|---------------------------|---------------------------|----------------------------|
| Application | Greenbelt                 | Greenbelt                 | Sidewalk                   |
| Static Load | 5,000 lbs.                | 5,000 lbs.                | 10,000/20,000 lbs.*        |

CHANNEL SGLB3048-24 & SGLB3048-36





**Satterman** engineers surveyors planners

VAULT DETAILS

FOR PERMIT USE ONLY

CHARTER FIBER OPTIC INSTALLATION RDOF - JN16E TOWN OF AZTALAN & LAKE MILLS JEFERSON COUNTY, WISCONSIN

C3.04

SHEET NO.

### CHARTER COMMUNICATIONS ENVIRONMENTAL / EROSION CONTROL NOTES

#### **GENERAL**

- 1. If WDNR permit was obtained for the project, all permit conditions shall be met during construction of the project. Contractor may go to: (http://dnr.wi.gov/regulations/environmental.html) for technical assistance on erosion control methods and environmental regulations used by WDNR.
- 2. No spoils or stock piles may be placed on any roadways, gravel shoulders or wetland areas. All excess spoils are to be removed from wetlands and placed in a suitable upland location.
- 3. If any spills (i.e. Gas, oil, Hydraulic fluid) occur on site, stop work and contact Charter Construction Supervisor immediately.
- 4. The contractor is responsible for the disposal of trench spoils, excess excavated and demolished materials.

#### **EROSION CONTROL**

- 5. If soil disturbance occurs on slopes or channels/ditches leading to wetlands or waterways, or within wetlands, the disturbed areas shall be stabilized and appropriate erosion control Best Management Practices (BMP) shall be implemented.
- 6. Guidance in the proper use of erosion and sediment control products for Charter contract work can be found in the WDOT Product Acceptability List (PAL) available at the following website: (http://www.dot.wisconsin.gov/business/engrserv/pal.html ). This list contains products that have been approved for use on State of Wisconsin airport, structure, and highway projects.
- 7. Where stock or spoil piles are allowed, Contractor it to establish and maintain perimeter erosion control around stock piles at all times. Silt fence, silt socks or equivalent will be required around the piles in order to prevent sediment runoff. During severe weather conditions, spoil piles may require tarpping or may be trucked off site and returned when needed.
- 8. Inspect installed erosion control BMPs at least one time per week and after 1/2-inch rain events; Repair as necessary.
- 9. All areas shall be temporarily stabilized within 14 days of last disturbance.
- 10. All stockpiles must be temporarily stabilized within 7 days of last disturbance.
- 11. All disturbed areas must be stabilized within 7 days of reaching final grade.
- 12. Erosion Mat Class 1 Urban Type A is required at all disturbed bore pit locations for all installations.

#### **CONTAMINATED SOILS**

13. Whenever soil exhibiting obvious signs of contamination (e.g. discoloration, petroleum or solvent odor, free liquids other than water, buried containers or tanks, or other obvious signs of environmental impacts) is encountered during excavation or installation, cease work immediately, take appropriate immediate precautions to ensure worker health and safety, and contact both the Charter Construction Coordinator and the Charter Construction Supervisor.

#### BORE PITS AND FRAC-OUT CONTINGENCY PLAN

- 14. Bore pits and stock piles will be protected on the down slope side with silt fence and silt socks to prevent seepage of boring fluids and sediment runoff contamination when work on slopes and/or wetlands.
- 15. A frac-out contingency plan shall be in place and implemented accordingly. The Contingency plan shall incorporate the following components.
  - a. Continuously inspect the bore path for frac-outs in order to respond quickly and appropriately. Containment Materials (e.g. silt fence, silt socks, sand bags, etc.) shall be on site and available should a frac-out occur.
  - b. Containment Materials (e.g. silt fence, silt socks, sand bags, etc.) shall be on site and available should a frac-out occur.
  - c. A vac truck shall be accessible in order to respond guickly to a frac-out.

#### **WETLANDS**

- 16. As much as practicable, the majority of work will be staged from the public roadways and road shoulders, keeping equipment out of adjacent wetlands.
- 17. All work will be conducted to minimize soil disturbance. no rutting will be allowed within the wetlands.
- 18. If soils are not frozen or stable to a point that avoids rutting, timber mats, mud tracks, or equivalent will be utilized to access work locations.
- 19. Excavated spoils will not be stockpiled in wetlands.
- 20. All excess spoils will be removed from wetlands and placed in a suitable upland location.
- 21. Trenching and pit excavations within wetlands will include soil segregation to facilitate restoration of pre-construction soil stratification, and restoration to pre-construction elevations.
- 22. If soil disturbance occurs on slopes leading to wetlands or within wetlands, the disturbed areas will be stabilized and appropriate erosion control Best Management Practices will be implemented.




**EROSION CONTROL NOTES** 


CHARTER FIBER OPTIC INSTALLATION RDOF - JN16E TOWN OF AZTALAN & LAKE MILLS JEFFERSON COUNTY, WISCONSIN

C4.01

#### **GENERAL NOTES**

- 1) TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- 2 WOOD POSTS SHALL BE A MINIMUM SIZE OF 11/8" X 11/8" OF OAK OR HICKORY.
- 3 CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) TWIST METHOD -- OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK METHOD -- HOOK THE END OF EACH SILT FENCE






GEOTEXTILE


FABRIC

FLOW DIRECTION 1

SILT FENCE TIE BACK (WHEN ADDITIONAL SUPPORT REQUIRED)







HOOK METHOD JOINING TWO LENGTHS OF SILT FENCE 4

EXCESS FABRIC TRENCH DETAIL \* NOTE: 8'-0" POST SPACING ALLOWED IF A

WOVEN GEOTEXTILE FABRIC IS USED.

SILT FENCE

This drawing based on Wisconsin Department of Transportation Standard Detail Drawing 8 E 9-6.

SILT FENCE

Batterman

**EROSION CONTROL DETAILS** 

CHARTER FIBER OPTIC INSTALLATION RDOF - JN16E TOWN OF AZTALAN & LAKE MILLS JEFFERSON COUNTY, WISCONSIN


SHEET NO.


C4.02

Batterman

C4.03

SHEET NO





Sediment Log

Graded Soil

2' (Typ)


of Where Logs Meet (Typ)

€ Ditch


- Locate Sediment Logs as indicated in plans, SWPPP or as directed by the Engineer.


  Select, install and maintain Logs per manufacturers' specifications and good engineering practices.

  Lay sediment log across prepared ditch or channel. Trenching or burial of Sediment Logs is not required. The close, continuous contact between the bottom of the Log and the ground is mandatory. The Logs shall be installed in the ditch, swale or channel bottom perpendicular to the flow of water as shown on detail this sheet.
- Stake Log as shown. Stakes shall be placed through downstream side only as shown
- DO NOT drive stakes through center of the log. Stakes must be driven into the ground as shown. Ensure that no gaps exist between soil and bottom of Sediment Log. Repair any rills or undercuts promptly.
- Placement of Sediment Logs shall be evaluated by the Engineer in rocky soil conditions.
- Remove Sediment Log BMPs within the ditches/channels and around the storm drain inlets as per the Direction of the Engineer or as soon as practicable upon stabilization of the construction disturbed area.
- Dispose of Sediment Logs and trapped sediment material and fill trench created by Sediment Log.
- 10. The installation and maintenance of Sediment Log BMPs shall not negatively impact traffic safety, nor the designed function of roadway or bridge drainage facilities. Sediment Logs shall be installed and maintained to carry the stormwater of at least 2-year, 24-hour events.
- 11. Field adjust and correct Sediment Log BMP immediately if it is causing flooding, erosion, and/or affecting roadway safety.



SEDIMENT LOG INSTALLATION DETAILS





**EROSION CONTROL DETAILS** 

engineers surveyors planners 2857 Bartells Dive Beloit, Wisconsin 53511 608365.464 www.rhbatterman.com

CHARTER FIBER OPTIC INSTALLATION RDOF - JN16E TOWN OF AZTALAN & LAKE MILLS JEFFERSON COUNTY, WISCONSIN

SHEET NO.

C4.04